

DP 705 WD2

PE 806/705WD/08.10

BUILT 31/08/2010, RECONDITIONED

Truck specifications

Power Train

MTU Detroit Diesel 12V2000 – DDEC IV, Tier2

567 kW (760 HP), 23.89 liter, electronic control

Allison H6610A transmission – automatic, electronic control, torque converter, six speeds forward, two reverse

Body and capacities

65.000 kg payload

42 m³ capacity—heaped SAE2:1

Standard body

Brakes

Dry disk brakes on the front axle

Oil-cooled wet-disk brakes on the rear axle, acting as a retarder, 81.600 cm² surface

ABS, ASR systems

Standard equipment

Oil pneumatic Perlini suspensions, 270mm

Central lubricating system

N.6 24.00R35” tires

Automatic air conditioning.

Sizes

Length 9830 mm

Width 4613 mm (including mirrors)

Height 4530 mm



Terms and conditions

Delivery

Ex-works at our workshop in Verona

Lead time

120 days after order confirmation

Warranty

Serimac warrants that the truck will conform with its intended design specifications at the time of sale, and be free from defects in material and workmanship related to our reconditioning for **six months or 1.500 working hours**—whichever comes first, from the startup of the product.

The warranty only covers the supply of parts recognized as defective by Serimac, and labor performed by Serimac or their service dealers.

The warranty does not cover:

- Parts subject to normal wear—such as filtering and braking elements, piping in general, tires, fuses, light bulbs, glass...
- Damage from misuse: Overloading, improper maintenance, accidents, off-spec fuels/lubricants, unapproved modifications.
- Any components or spare parts not installed on the truck at the time of sale or supplied by Serimac.
- Electrical system faults, unless directly caused by Serimac.

Startup

Serimac will handle the startup of the equipment, as well as provide training for its maintenance and correct usage

SE.RI.MA.C s.r.l.

Serimac Srl – www.serimac.net

Via Alberazzi 28, 37030 Veronella-VR

Phone: +39 0442 480378 – serimacsrl@gmail.com